

Part No.: V211-001

Name: Steel 3 Step Stairway (700 wide)

Weight: 45 kg


Standard: EN 12811-1 Material: Galvanised Steel


Dimensions: mm




This Technical Document must always be used in conjunction with **HAKI's General Qualifications** -See below

- 1. Always plan your work and installation
- 2. Always select the right equipment
- 3. Always regularly inspect your system









www.HAKI.com


**©HAKI** 








## **Transport Lengths**




www.HAKI.com






\* Complies to EN 12811-1 between 41° - 49°

Slab Fixings			
Angle (a°)	X	Υ	
30	934	530	
35	886	604	
40	831	674	
41	819	687	
45	769	738	
49	716	785	
50	702	797	
55	630	850	





\* Complies to EN 12811-1 between 41° - 49°

Scaffold Fixings				
Angle (a°)	Χ	Υ		
30	887	476		
35	842	551		
40	791	623		
41	780	636		
45	734	689		
49	684	739		
50	671	750		
55	603	806		


Χ

www.HAKI.com


**©HAKI** 2246 - Subject to changes



- Loosen eye nuts Erect to desired angle Tighten eye nuts



- 4. 5.
- Mount guard rails Fit retaining pin



≤ 9








≥12 6b.

7a.

V212-015 Steel Stairway Slab Fix

min. 2





7b.


V212-024 Stairway Scaffold Fix HD (Pair)


















max. 2



## Joining Stairways - Max. 21 Steps












## Stairways support - 18 & 21 steps












www.HAKI.com



## **Spare parts**




**V212-024**Stairway Scaffold Fix HD (Pair)






**V212-022** Stairway lock Pair



**V212-014** Stairway - Standard step handrail



**V214-018**Stairway Lifting Rings Set of 4





For other parts and more information, please contact vertemax.

www.HAKI.com



## **General Qualifications**



These General Qualifications are applicable to all HAKI products and must always be read in conjunction with each products Technical Documentation (TD).

#### General

- Always check general product condition before use
- If in doubt always ask by contacting a representative of HAKI
- Reject any damaged or rusty components
- HAKI products and systems provide temporary protection during construction activity.
- HAKI products are NOT tested or intended:
  - to withstand impact by any vehicle,
  - to support or provide control of the public,
  - for the containment of bulk materials.

### **Always Plan your works**

- Take note of location, proximity to permanent and temporary hazard structures.
- Take note of dimensions, layout and access areas.
- Always identify both the fall hazard for the installer and the falling materials hazard for persons and property below.
- These identified hazards should also be considered on dismantling.
- HAKI strongly recommends seeking competent Work at Height advice if in any doubt about the installer's or other's safety.
- Note the component weight as given on the TD sheets and ensure suitable handling equipment is available.
- Ensure local site Risk Assessment / Method Statement detail is observed and followed.

### **Fixing selection**

- All fixings should be confirmed as suitable for the chosen application site.
- Material type and thickness, edge proximity, depth of embedment, and proximity to other fixings, all impact the strength of a fixing. Please refer to manufacturer's instructions for fixing guidance and limitation.
- The dimensions for installation and the load capacity should be confirmed by the fixing manufacturer for each application.
- Competent fixings advice should be sought if in any doubt.

#### Fine mesh containment

- Note that the addition of any fine containment mesh (such as on barriers or safety nets) increases the wind load attracted to the supports.
- Technical advice must be sought before any such addition.

#### Weather

- HAKI products and systems can be adversely impacted by significant wind speeds. Please
  note limitations on product TD and take any recommended remedial action. If in doubt,
  contact a HAKI representative.
- If in doubt, cease work, and use additional protection measures as required.
- All safety systems should be kept clear of ice and snow.

### **Inspection**

- All installed systems should be checked at least once every 7 days by a competent person, to ensure its continued integrity and that there are no signs of any potential failing.
- We recommend that these checks are recorded in a site log.
- Please ensure any defective product identified during inspection is replaced immediately.

#### Loading

- Any HAKI products subjected to loading, or used in anger, should be assessed to ensure it
  continues to provide the necessary protection. If this involves removing from service you
  must ensure the area is otherwise protected.
- The system should then be fully inspected, any components replaced as necessary, and the installation confirmed as fit for continued use by a competent person.

#### **Storage**

- HAKI recommends the use of its own storage and transit solutions.
- Take careful note of lifting and loading limits.
- All components should be stored in a manner that limits any detrimental environmental effect
  - due to weather or corrosive substances.

### **Traceability**

All HAKI products are traceable.

Key		
	Symbol	Meaning
1.	Symbol	Tech Data
1.		redit Butu
2.	€ <b>—</b>	If in doubt, check online @ www.HAKI.com
3.	? <u>···</u> ) → [·)	If in doubt call HAKI on +44 (0)1227 711072
4	!	Always Check/ Always confirm
5	(A)	Fall Hazard
6		Do this
7	X	Don't do this
8	<u></u> ✓	Be Aware
9	43	Recycle damaged materials
10	<b>↑ ?  </b>	Recommended Distance

4.4		C 16 : 1 6 19
11		Secure yourself against falling
12		Protect those below from falling equipment
13		Catch fan – Keep Clean from snow
14		Sheer Load
15		Tensile Load
16	<b>9</b>	Moment Load
17		Max Wind Load
18	+7	Check Weekly
19	Ţ	Insert
20	*	Install
21	? Nm	Torque Spanner and settings

	<del>,</del>	
22		Flat Head Screwdriver
23		Cross Head/Phillips Screwdriver
24	9	Tighten
25		Untighten
26		Tighten by hand
27	+ + +	Drill and select appropriate anchor
28		Floor/General
29		Concrete slab/floor
30		Timber Beam
31	75-130	Alu Beam